

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____	
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	T. <u>44</u> N. <del>XX</del> S., R. <u>34</u> <del>XX</del> W.	16a & 16b	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____	
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 25, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner 16a (East M.C. on Net River between Sections 6 & 7, T44N, R34W):
    - Wood post (Not found. No subsequent monuments found.)
    - Fir 6 S76E 16 ( " " " " accessory " )
    - W. Pine 30 N50E 55 (Found. " " " " )
  - Corner 16b (West M.C. on Net River between Sections 6 & 7, T44N, R34W):
    - Wood post (Not found. No subsequent monuments found.)
    - Fir 6 S53W 13 ( " " " " accessory " )
    - Cedar 6 N54W 13 ( Probably found. No subsequent accessory found.)

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner 16a: Recovered from original BT noted above. As position for corner now falls in the river, a monument was placed on the river bank 13.2 ft. due E of the true point. BT is a burned stump with lower blaze and notch plain, but no scribe marks.
  - Corner 16b: Recovered from probable original BT noted above, now a rotted stump with no marks, but presumed to be the BT because a corner placed from it bears N89°53'W 2.896 ch. from a positively identified original M.C. on E bank of river, the record distance being 2.83 ch.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner 16a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap for Witness Corner.
    - W. Birch 8 N32½° E (mag.) 28.5 ft. "MC, NBT"
    - Cherry 6 S61°E (mag.) 16.5 ft. "MC, NBT"
  - Note: NBT's are for the witness monument, not the true corner.
  - Corner 16b: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
    - W. Spruce 10 S27°W (mag.) 40.5 ft. "MC, NBT"
    - W. Spruce 13 N28°W (mag.) 85.2 ft. "MC, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

