

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> <sup>N.</sup> <del>XX</del> , R. <u>34</u> <del>XX</del> <sup>W.</sup>	E4
2. PROPERTY CONTROLLING IN SECTION	<u>8</u> , T. <u>44</u> <sup>N.</sup> <del>XX</del> , R. <u>34</u> <del>XX</del> <sup>W.</sup>	14
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> W.	
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 9, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E4 (1/4 corner between Sections 8 & 9, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Y. Birch 12 N58E 28 ( " " " " accessories " )  
 Fir 10 S40W 31 ( " " " " " " )

**Corner 14: (South 1/16 Corner between Sections 8 & 9, T44N, R34W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner E4:** Re-established on line between Sec. Cor. 39.694 ch. to N and to S. It is unlikely that this is the original corner position, as it falls alongside a large white pine stump, which was probably a sizeable living tree at the time of the original survey; however, I can find no way to determine the exact original corner location.

**Corner 14:** Established on line between Sec. Cor. 19.847 ch. S and 1/4 cor. 19.847 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner E4:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 6 S85° W (mag.) 6.5 ft. "1/4S, NBT"  
 Red Maple 7 S85° E (mag.) 12.2 ft. "1/4S, NBT"

**Corner 14:** 1" I. D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Sugar Maple 14 S38°E (mag.) 5.6 ft. "1/16S, BT"  
 Sugar Maple 6 N18°E (mag.) 32.3 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977

MICHIGAN REGISTERED LAND SURVEYOR  
A. O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

