

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{W.} E.	E6 & F7	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E., W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E., W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner E6 (1/4 corner between Sections 16 & 17, T44N, R34W):**
 Wood post (Not found. See B for subsequent monument.)
 Y. Birch 12 S47W 18 (" " No subsequent accessories found.)
 Fir 10 S86E 10 (" " " " " ")
- Corner F7 (1/4 corner between Sections 16 & 21, T44N, R34W):**
 Wood post (Not found. See B for subsequent monuments)
 Sugar 10 N82W 28 (" " No subsequent accessories found.)
 Sugar 12 S40E 44 (" " " " " ")
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner E6:** Re-established 11/8/76 on line between Sec. Cor. 40.070 ch. N and M.C. 20.271 ch. S. This position agrees with the record distance to foot of hill about 10 ch. N. Found a 3" x 3" x 4' squared cedar post rotted off at ground level, N74°W 15.8 from the corner, but nothing to indicate it was anything more than a forester's approximate corner.
- Corner F7:** Re-established 10/28/76 on line between Sec. Cor. 40.024 ch. to E and to W. Found an L. E. S. post N70°E 81.1 ft. and a recent 2" x 2" x 4' squared maple post N63°E 63.1 ft., each purporting to represent this corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner E6:** 1" I.D. x 39" iron pipe with 3 3/4" aluminum cap.
 W. Spruce 9 N63°E (mag.) 2.7 ft. "1/4S, NBT"
 W. Spruce 7 S69°W (mag.) 22.5 ft. "1/4S, NBT"
- Corner F7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 9 S71°E (mag.) 7.4 ft. "1/4S, NBT"
 Sugar Maple 10 S11°W (mag.) 10.9 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

