

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> ^{N.} XX , R. <u>34</u> ^{XX} W.	D5
2. PROPERTY CONTROLL- ING IN SECTION_____	<u>8</u> , T. <u>44</u> ^{N.} XX , R. <u>34</u> ^{E.} W.	15
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ ^{N.} S., R. _____ ^{E.} W.	
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 3, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D5 (1/4 corner between Sections 8 & 17, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Fir 6 N10E 7 (" " " " accessories ")
 Fir 8 S70E 16 (" " " " " ")

Corner 15 (West 1/16 corner between Sections 8 & 17, T44N, R34W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D5: Re-established on line between Sec. Cor. 40.099 ch. to E and to W.
 Corner 15: Established on line between Sec. Cor. 20.050 ch. W and 1/4 cor. 20.050 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D5: 1" I. D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.
 B. Spruce 7 N 9°W (mag.) 5.9 ft. "1/4S, NBT"
 B. Spruce 6 S21°E (mag.) 4.4 ft. "1/4S, NBT"

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4 aluminum cap.
 Red Maple 6 N35°W (mag.) 57.8 ft. "1/16S, BT"
 Red Maple 6 S26°E (mag.) 25.3 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

