

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLL- ING IN SECTION <u>8</u> , T. <u>T44</u> N. <u>XX</u> R. <u>34</u> <u>XX</u> W.	N. S., R. _____ E. W.	3a & 3b
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 3a (South M.C. between Sections 7 & 8, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Cedar 16 S 4E 14 (" " " " accessories ")
 Fir 12 S62W 35 (" " " " " ")

Corner 3b (North M.C. between Sections 7 & 8, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Fir 10 N35W 7 (" " " " accessories ")
 Fir 10 N40E 15 (" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 3a: Re-established 6/25/76 on S bank of Paint River by working back along presumed original meander line from the confluence of the Paint and Net Rivers, which was reported to be N36°W 3.25 ch. from this corner. As the meanders were run after the M.C.'s on the sec. line were established, it is believed that this procedure represents the best means of determining the location of the sec. line between Sec. 7 & 8 at this place.

Corner 3b: Re-established 11/12/76 on true Sec. Line on N bank of Paint River, 3.400 ch. N of South M.C. between 7 & 8 and 34.479 ch. S of Sec. Cor. 5, 6, 7, & 8. Original notes say it was 2.60 ch. bet. M.C.'s, but this is patently incorrect.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 3a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.
 Black Ash 12 S56°W (mag.) 13.5 ft. "MC, NBT"
 W. Spruce 12 S 3°E (mag.) 44.1 ft. "MC, NBT"
 Also squared & scribed a 12" B. Ash on bank of river N89°W 2.5 ft., to center of tree.

Corner 3b: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.
 Cedar 10 S86°E (mag.) 20.5 ft. "MC, NBT"
 Cedar 7 N47°E (mag.) 18.0 ft. "MC, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 27, 1977

CHIEF OF SURVEY PARTY
Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger



Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581