

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 44 ^{N.} S. R. 34 ^{W.} E.	C 3
2. PROPERTY CONTROLLING IN SECTION _____ 8	T. 44 ^{N.} S. R. 34 ^{W.} E.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 12, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C3 (Section Corner 5, 6, 7, & 8, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Tamarack 24 N85E 16 (" " " " accessories ")
 Fir 10 S44W 29 (" " " " " ")

Corner 3 (North 1/16 corner between Sections 7 & 8, T44N, R34W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C3: Re-established on line between South M.C. between Sec. 7 & 8 which is 37.879 ch. S and Sec. Cor. 5, 6, 31, & 32, T44-45N, R34W which is 78.925 ch. N. Because of an excess of 1.574 ch. in this interval as compared to the original distance, the question arose as to how to properly distribute the difference. I judged that a position on the straight line at the latitude of an original M.C. on Net River 25.638 ch. due West would most nearly approximate the original corner position and so established it at that point.

Corner 3: Established on line between South M.C. between Sec. 7 & 8 16.539 ch. S and Sec. Cor. 5, 6, 7, & 8 21.340 ch. N. This results in a distance to 1/4 cor. 7 & 8 of 21.169 ch., thus dividing the North 1/2 mile into approximately equal parts.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Cedar 14 S85°W (mag.) 6.6 ft. "S7, NBT"
 Cedar 12 N46°E (mag.) 36.4 ft. "S5, NBT"

Corner 3: 1" I. D. x 36" iron pipe with 3 3/4" aluminum cap.
 W. Spruce 12 N72°E (mag.) 16.1 ft. "1/16S, BT"
 W. Spruce 13 N41°W (mag.) 16.2 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 27, 1977

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

