

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. <u>34</u> R. <u>34</u> E W.	E7
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 28, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E7 (Section Corner 16, 17, 20, & 21, T44N, R34W):

Wood post	(Not found. See B for subsequent monument.)
Sugar 18 S37½W 20	(" " No subsequent accessories found.)
Fir 12 N17E 60	(" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner re-established on E'ly extension of a line from an original Sec. Cor. 79.985 ch. W through a living original Y. Birch line tree 19.373 ch. W. I believe this is as close to the original corner position as one can get, as the field notes describe the corner as having been set "in ravine N & S Bottom of hill," and that when beginning the next mile to the east, the line begins "to ascend hill" and at 3.00 ch. is at the "top of hill 30 feet high." As re-established, the corner fits this description exactly. A Land Economic Survey control post, dating back to the mid-1930's, is located S71°25.5'E 50.1 feet from this corner position, but as it is on the side of the hill, and considerably misaligned with the line tree and section corner to W, I deemed it unacceptable as (over)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Sugar Maple 8	S48°W (mag.)	11.0 ft.	"S20, NBT"
Red Maple 8	N52°E (mag.)	13.7 ft.	"S16, NBT"
Cedar 17	S70°E (mag.)	27.4 ft.	"S21, NBT"

Note: Distances are horizontal.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977

CHIEF OF SURVEY PARTY
Arthur O. Enger
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

