

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>8</u>	T. <u>44</u> N. S., R. <u>34</u> E. W.	16 & 16a
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 16 (East 1/16 corner between Sections 8 & 17, T44N, R34W):

Not established in original survey nor subsequently, apparently.

Corner 16a (West M.C. between Sections 8 & 17, T44N, R34W):

Wood post (Not found. No subsequent monuments found.)
Cedar 14 S8W 56 (" " " " accessories ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 16: Established 11/8/76 on line between Sec. Cor. 20.049 ch. E and 1/4 cor. 20.049 ch. W.

Corner 16a: Re-established 11/4/76 on W bank of Paint River on line between 1/4 cor. 11.227 ch. W and Sec. Cor. 29.795 ch. E. These distances do not fit the original field notes well, but there appears to be no way to reconcile them, as the total distance for the mile does not agree with the record, either.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Sugar Maple 5 N71°W (mag.) 23.1 ft. "1/16S, BT"
Red Maple 6 S41°E (mag.) 15.6 ft. "1/16S, BT"

Corner 16a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Thornapple 5 N68°W (mag.) 8.8 ft. "M.C., NBT"
Elm 7 S37°W (mag.) 30.9 ft. "M.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

