

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>34</u> E. <u>X</u> R. _____ W. _____	<u>K-13 & L-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K13 (Section Corner 1, 2, 35 & 36, T43-44N, R34W):
 Sugar post (Not found. No subsequent monuments found.)
 Sugar 10 N59-1/2E 46 (Not found. No subsequent monuments found.)
 Sugar 12 S75 E 48 (Not found. No subsequent accessories found.)
 Sugar 9 S65 W 28 (Not found. No subsequent accessories found.)
 Lynn 18 N32 W 17 (Not found. No subsequent accessories found.)

Corner L13 (1/4 corner between Sections 1 & 36, T43-44N, R34W):
 Cedar post (Not found. Found wood post approx. corner)
 Y. Birch 14 N13W 17 (Not found. No subsequent monuments found.)
 Fir 7 N82E 48 (Not found. No subsequent monuments found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K13: Restored 8-16-79 proportionately on an E & W latitudinal line between Twp. Cor. 80.0015 ch. E and Sec. Cor. 240.0045 ch. W.
Corner L13: Restored 8-20-79 proportionately on an E & W latitudinal line between Twp. Cor. 40.001 ch. E and Sec. Cor. 280.005 ch. W. Found a 4" x 4" x 6' squared cedar post, apparently in place for perhaps 10 years, with another older post lying on ground nearby, at a point S27°40'E 24.1 ft. from corner reported herein, but found no physical or measurement support for it (them) as being at the original corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K13: 1" I.D. x 36" iron pipe with 3-3/4" aluminum cap.
 Sugar Maple 15 N 3°W (mag.) 18.4 ft. "S35, NBT"
 Sugar Maple 12 S72°E (mag.) 14.8 ft. "S 1, NBT"
 Sugar Maple 13 S61°W (mag.) 24.3 ft. "S 2, NBT"
 Declination 0°35' West.
Corner L13: 1" I.D. x 36" iron pipe with 3-3/4" aluminum cap.
 Double Red Maple 7 S71°E (mag.) 53.7 ft. "1/4S, NBT"
 Red Maple 6 N51-1/2°E (mag.) 28.2 ft. "1/4S, NBT"
 Distances horizontal. Declination 0°40' West.

SIGNED BY _____ DATE _____

Carl R. Johnson

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE January 25, 1980

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

