

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--:                            | IRON COUNTY<br>LOCATED IN--:                                | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____                  | T. <u>44</u> N. <del>XX</del> R. <u>34</u> <del>XX</del> W. | K-12               |
| 2. PROPERTY CONTROLLING IN SECTION <u>36</u> | T. <u>44</u> N. <del>XX</del> R. <u>34</u> <del>XX</del> W. | 3                  |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____   | T. _____ N. _____ R. _____ E. _____ W. _____                |                    |
| 4. LOT NO. _____, RECORDED PLAT _____        |   |                    |
| 5. PRIVATE CLAIMS _____                      |   |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 16, 19 79, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner K12 (1/4 corner between Sections 35 & 36, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Y. Birch 10 N35E 34 (Not found. No subsequent accessories found.)  
 Sugar 7 S29W 29 (Not found. No subsequent accessories found.)

**Corner 3 (North 1/16 corner between Sections 35 & 36, T44N, R34W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner K12:** Restored on line between Section Corners 39.5695 ch. to N and to S.  
**Corner 3:** Established on line between 1/4 cor. 19.7845 ch. S and Sec. Cor. 19.7845 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner K12:** 1" I.D. x 36" iron pipe with 3-3/4" aluminum cap.  
 Sugar Maple 12 S71°E (mag.) 15.2 ft. "1/4S, NBT"  
 Sugar Maple 7 N39°E (mag.) 25.2 ft. "1/4S, NBT"  
 Declination 0°20' East.

**Corner 3:** 1" I.D. x 36" iron pipe with 3-3/4" aluminum cap.  
 Sugar Maple 4 N59°W (mag.) 4.0 ft. "1/16S, BT"  
 Sugar Maple 7 S51°E (mag.) 50.5 ft. "1/16S, BT"  
 Declination 1°00' East.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

Carl R. Johnson

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

*Arthur O. Enger*  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Arthur O. Enger

DATE January 23, 1980

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

