

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> <sup>N.</sup> <del>X</del> , R. <u>34</u> <sup>E.</sup> <del>W.</del>	<u>I-13 &amp; J-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S., R. _____, E., W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S., R. _____, E., W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner I-13 (Section Corner 2, 3, 34, & 35, T43-44N, R34W):**

- Ironwood post (Not found. No subsequent monuments found.)
- Y. Birch 12 N10E 14 (Not found. No subsequent accessories found.)
- Y. Birch 10 S15W 67 (Not found. No subsequent accessories found.)
- Sugar 6 N45W 15 (Not found. No subsequent accessories found.)
- Ironwood 8 S25E 59 (Not found. No subsequent accessories found.)

**Corner J-13 (1/4 corner between Sections 2 & 35, T43-44N, R34W):**

- Iron post (Not found. No subsequent monuments found.)
- Sugar 18 N39W 14 (Not found. No subsequent accessories found.)
- Sugar 6 N38E 20 (Not found. No subsequent accessories found.)

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner I-13: Restored 8-20-79 proportionately on an E & W latitudinal line between Twp. Cor. 160.003 ch. E and Sec. Cor. 160.003 ch. W.**

**Corner J-13: Restored 8-16-79 proportionately on an E & W latitudinal line between Twp. Cor. 120.002 ch. E and Sec. Cor. 200.004 ch. W.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner I-13: 1" I.D. x 36" iron pipe with 3-3/4" aluminum cap.**  
 Sugar Maple 6 S33°E (mag.) 27.8 ft. "S2, NBT"  
 Sugar Maple 7 N13°E (mag.) 37.3 ft. "S35, NBT"  
 Declination 0°40' West.

**Corner J-13: 1" I.D. x 36" iron pipe with 3-3/4" aluminum cap.**  
 Sugar Maple 9 N73°E (mag.) 25.4 ft. "1/4S, NBT"  
 Sugar Maple 6 S55°E (mag.) 20.2 ft. "1/4S, NBT"  
 Declination 0°35' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
Carl R. Johnson

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE \_\_\_\_\_  
CHIEF OF SURVEY PART

APPROVED AND SIGNED BY Arthur O. Enger DATE January 25, 1980  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

