

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	(IRON COUNTY) LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>34</u> W.	F-13 & G-13
2. PROPERTY CONTROLL- ING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 21, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner F13 (1/4 corner between Sections 4 & 33, T43-44N, R34W):**
 Sugar post (Not found. Found monument for approx. cor.)
 Sugar 14 N50E 17 (Not found. No subsequent accessories found.)
 Lynn 8 N53W 35 (Not found. No subsequent accessories found.)
- Corner G13 (Section Corner 3, 4, 33, & 34, T43-44N, R34W):**
 Sugar post (Not found. No subsequent monuments found.)
 Sugar 12 N23E 19 (Not found. No subsequent accessories found.)
 Cedar 12 N80W 38 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner F13:** Restored proportionately on an E & W latitudinal line bet. Twp.
 Cor. 280.005 ch. E and Sec. Cor. 40.001 ch. W. Found a 4' high steel fence post N14°10'E 15.3 ft., set by unknown persons, evidently intended to mark the approximate location of the corner.
- Corner G13:** Restored proportionately on an E & W latitudinal line bet. Twp.
 Cor. 240.0045 ch. E and Sec. Cor. 80.0015 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner F13:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 9 N19°W (mag.) 21.5 ft. "1/4S, NBT"
 Sugar Maple 5 S17°E (mag.) 27.4 ft. "1/4S, NBT"
 Declination 0°40' West.
- Corner G13:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 10 N13°E (mag.) 30.5 ft. "S34, NBT"
 Sugar Maple 7 S71°E (mag.) 38.6 ft. "S 3, NBT"
 Declination 0°40' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 28, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

