

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF -- | (IRON COUNTY) LOCATED IN -- | CORNER CODE NUMBER |
|--|---|------------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>44</u> N. <u>X</u> R. <u>34</u> W. | <u>H-13 & I-12</u> |
| 2. PROPERTY CONTROLLING IN SECTION _____ | T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 20, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner H13 (1/4 corner between Sections 3 & 34, T43-44N, R34W):**
 - Sugar post (Not found. Found forester's picket approx. cor.)
 - Fir 8 N65E 12 (Not found. No subsequent accessories found.)
 - Fir 8 N24E 28 (Not found. No subsequent accessories found.)
 - Corner I12 (1/4 corner between Sections 34 & 35, T44N, R34W):**
 - Wood post (Not found. No subsequent monuments found.)
 - Sugar 10 S42E 17 (Not found. No subsequent accessories found.)
 - Sugar 8 N63W 22 (Not found. No subsequent accessories found.)

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner H13:** Restored proportionately on an E & W latitudinal line bet. Twp. Cor. 200.004 ch. E and Sec. Cor 120.002 ch. W. Found a forester's approx. corner picket N71°W 4.7 ft.
 - Corner I12:** Restored on line between Sec. Corners 39.7005 ch. to N and to S.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner H13:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 5 N40°E (mag.) 25.6 ft. "1/4S, NBT"
 Red Maple 11 S40°E (mag.) 14.3 ft. "1/4S, NBT"
 Declination 0°55' West.
 - Corner I12:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 12 N80°E (mag.) 37.0 ft. "1/4S, NBT"
 Sugar Maple 10 S44°E (mag.) 28.0 ft. "1/4S, NBT"
 Declination 0°30' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 28, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

