

79

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Iron \_\_\_\_\_  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S 9 T 44 R 34N 15  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

Mar 20 1995

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					●								
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
West 1/16 Corner between Sections 9-16. Corner not established in the original survey. Corner monumented in 1976 by A.O. Enger as follows: "Established 11/9/76 on line between Sec. Cor. 19.829 ch. W and 1/4 cor. 19.829 ch. E. Found a 3"x3"x3.5' squared cedar post N39E 36.3'. Set 1" I.O.x36" iron pipe with 3 3/4" aluminum cap. Sugar Maple 4 S9W 10.5', Sugar Maple 5 N68W 12.8', Red Maple 5 N75E 2.9". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the 1976 monument, as described, in good condition, and at record bearing and distance from the 1976 witnesses. Determined that the corner position was erroneously monumented in 1976. I found the 1976 monument to be nearly due west, 21.5' from the position described as having been established in 1976. I removed the 1976 monument and monumented the proper position: midway and on a straight line between Section corner 1308.28' west and Quarter corner 1308.28' east. At this position, I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 1" pipe with 4" MDNR cap

Blazed and scribed the following bearing trees:

12" Sugar S63E 24.4'    1/16S BT"  
10" Sugar S14W 6.1'    1/16S BT"  
5" Sugar N53W 16.1'    1/16S BT"  
14" Hemlock N05E 51.6'    1/16S BT"

Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 3/20/96  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division