

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>34W</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:12

L.C. Records: L.8, P.24

*Gary L. Pisoni*  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 29 and 30, T44N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 18, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

Elm	14"	N 25° W	25 lks (16.50 feet)
Sugar	14"	S 50° E	37 lks (24.42 feet)

PEER GROUP APPROVED

Iron County Peer Group 12-31-99  
COUNTY REPRESENTATIVE

On 8/29/77, Arthur O. Enger, RLS, DNR, restored the corner position on line and midway between the Northeast and the Southeast Section Corners of Section 30, set a 1" diameter by 24" long iron pipe with a 3 3/4" aluminum cap stamped as follows:

T44N, R34W, 1/4, S-30, S-29, 8/29/77, RLS 13581 and recorded in Liber 1, Page 551 of LC records.

1977 Bearing Trees:

Sugar Maple	5"	S 41° E	24.1 feet
Red Maple	13"	N 64° W	46.9 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/10/99, found monument as described above and the following bearing trees:

Sugar Maple	7"	S 41° E	24.22 feet
Sugar Maple	13"	N 64° W	47.42 feet

Monument is located on the East shoulder of a county road and 12" below roadbed surface.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Basswood	8"	N 56° E	30.80 feet
Ash	7"	S 53° W	54.51 feet
Steel sign post		East	9.8 feet

99-24  
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

