

RE

MAR 9 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Iron (County), Located In, Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling, etc.

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 30 AM 10:13
L.C. Records: L.S. P. 25
[Signature]

Register of Deeds Stamp & File Number

4. Lot No.
5. Private Claims

Section corner to Sections 29, 30, 31, 32, T44N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a dot in row 11, column B.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 18, 1851 by Guy H. Carleton, U.S. Deputy Surveyor

Original Corner; Wood Post

Original Bearing Trees:

Table with 4 columns: Tree type, Diameter, Bearing, Distance. Includes Sugar 6" N 14° W 14 lks (9.24 feet) and Sugar 12" S 28° E 38 lks (25.08 feet).

PEER GROUP APPROVED

[Signature] 12-21-99
COUNTY REPRESENTATIVE

On 8/29/77, Arthur O. Enger, RLS, DNR, restored the corner position by double proportionate measurements and set a 1" diameter by 24" long iron pipe with a 3 3/4" aluminum cap stamped as follows:

T44N, R34W, S-29, S-30, S-31, S-32, 8/29/77, RLS 13581 and recorded in Liber 1, Page 552 of LC records.

1977 Bearing Trees:

Table with 4 columns: Tree type, Diameter, Bearing, Distance. Includes Sugar Maple 10" S 60° W 52.4 feet, Red Maple 12" N 33° W 36.9 feet, Red Maple 12" S 58° E 55.7 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/10/99, found iron pipe as described above, bent and twisted, aluminum cap destroyed due to grading of gravel road.

Found the following bearing trees:

Table with 4 columns: Tree type, Diameter, Bearing, Distance. Includes Red Maple 15" S 58° E 56.30 feet, Sugar Maple 13" S 63° W 52.52 feet, Red Maple (dbl) 11" N 35° W 37.21 feet.

Corner located in the West lane of county road.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced the above damaged monument with a 5/8" diameter by 30" long rebar and a 3" diameter aluminum cap stamped as follows: (said monument located 6" below roadbed surface) Iron County Remonumentation, T44N, R34W, S-29, S-30, S-31, S-32, 1999, RLS 27457, from which the following bear: (All measurements taken to north side of tree)

Table with 4 columns: Monument type, Diameter, Bearing, Distance. Includes Sugar Maple 12" N 75° E 41.54 feet, Steel sign post N 80° W 15.8 feet.

99-25

Signed by [Signature] Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 23, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

