

FEB 22 1996

COMMISSION

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

95 DEC 15 PM 2:21

LC Records L6, P 408

Silvestre
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T43N R34W T44N R34W T___ R___ T___ R___	C-1 C-13 ✓
2. Property Controlling in Section	S___ T___ R___ S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___ S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 31 & 32 T44N R34W
6 & 5 T43N R34W

I, Gary L. Pisoni, in a field survey on Sept. 12, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S Deputy Surveyor on 9/12/1846.
 Original corner: Maple Post
 Original bearing trees:

Hemlock	30"	N 65° E	15 links (9.90 feet)
Yellow Birch	6"	N 43° W	16 links (10.56 feet)
Yellow Birch	6"	S 37° W	29 links (19.14 feet)
Sugar	12"	S 28° E	32 links (21.12 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Found a 3/4" x 15" iron pin located in the centerline of a road intersection. Iron pin found by Robert E. Schmeling RLS on July 20, 1981 and recorded by Schmeling in Liber 2B of L.C. Records, Page 42 on 12/15/1981. I accept the iron pin as the best available evidence for restoring the corner position.

Monument is 8 inches below road bed surface.

ACT 74 Research on file with County Representative

PEER GROUP APPROVED

Gary L. Pisoni 12-14-95
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T44N, R34W, S-31, S-32, S-6, S-5, T43N, 1995, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Utility Pole		N 54° E	38.46 feet
Hemlock	17"	S 42° E	58.26 feet
Red Maple	12"	S 47° W	66.96 feet
Rebar	5/8"x30"	N 36° W	45.30 feet
Drill Rod (Exist)	1"dia.	S 89° E	32.60 feet

Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date 11-30-95

