

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>34W</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:13
L.C. Regarde: L.S. P. 26
Gary L. Pisoni
REGISTERED PROFESSIONAL SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner to Sections 29 and 32, T44N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 18, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

Yellow Birch	10"	S 15° E	1.05 chs (69.3 feet)
Lynn	12"	N 25° W	70 lks (46.20 feet)

PEER GROUP APPROVED

Don Ray Pisoni 12-21-99
COUNTY REPRESENTATIVE

In March, 1947, R. Mitchell and N.J. Peryam found a squared maple, a fence corner and yellow birch bearing tree.

On 12/9/53, D. Buell and H. Gerry found the above evidence of 1947 and set an iron pipe with a brass cap from the yellow birch bearing tree, stamped as follows: Northern Paper Mills, 1/4, S-29, S-32 and recorded in Liber 2, Page 36 of LC records.

1953 Bearing Trees:

Maple	12"	N 87° E	29 lks (19.14 feet)
Maple	14"	S 11° W	38 lks (25.08 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/10/99, found the above described monument, 18" above ground surface and the following bearing trees (both bearing trees are now decayed stumps):

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced the above described monument with a 5/8" diameter by 30" long rebar and a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T44N, R34W, 1/4, S-29, S-32, 1999, RLS 27457 from which the following bear: (All measurements taken to a nail in side of bear)

Sugar Maple	8"	N 23° W	17.08 feet
Sugar Maple	9"	N 52° E	15.83 feet
Sugar Maple	7"	S 35° E	20.20 feet
Sugar Maple	7"	S 48° W	23.25 feet
Steel sign post		S 67° E	0.8 feet

99-26

Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

