

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>34W</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:10  
L.C. Records: L. 8, P. 11  
*[Signature]*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner Section 16, 17, 20, 21, T44N, R34W

I, Gary L. Pisoni, in a field survey on Mar. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 2, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.  
Original Corner: Wood Post  
Original Bearing Trees:  
Sugar 18" S 37 1/2°W 20 lks(13.20 feet)  
Fir 12" N 17°E 60 lks(39.60feet)

PEER GROUP APPROVED  
IRON Bay Run 12-31-99  
COUNTY REPRESENTATIVE

On 10-28-76, Arthur Enger, RLS, re-established corner on E'ly extension of a line from original Sec. Cor. 79.985 ch. W. through a living original Y. Birch line tree 19.373 ch. W. Set a 1" diameter by 36" long iron pipe with a 3 3/4" aluminum cap and stamped as follows: T44N R34W, S-16, S-17, S-20, S-21, 10-28-76, RLS-13581 and recorded in L.1, Pg.545-546.  
1976 Bearing Trees:

Sugar Maple	8"	S 48°W	11.00 feet
Red Maple	8"	N 52°E	13.70 feet
Cedar	17"	S 70°E	27.40 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 3/10/99, found monument as described above and the following bearing tree:  
Sugar Maple 10" S 48°W 11.16 feet

County record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Basswood	13"	N 34°W	10.81 feet
Sugar Maple	11"	N 11°E	22.26 feet
Sugar Maple	5"	N 67°E	12.99 feet
Steel sign post		N 38°E	0.85 feet

99-11  
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
27457 REVISION MAY 14, 1975  
REVISION JAN., 1983  
REVISION OCT., 1995

