

SURVEY & REMONUMENTATION

JAN 18 1998

SECTION

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PM 1:30
L.C. Records 6.7 P. 163

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Gary L. Pisoni
REGISTERED SURVEYOR

For corners in

Iron
(County)

Located In:

Corner Code #

- 1. Public Land Survey T44N R34W
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

E-11

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner Common to Sections 28, 29, 32 and 33, T44N, R34W

I, Gary L. Pisoni, in a field survey on November 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner: Wood Post

Original Bearing Trees:

Sugar	16"	S 54 1/2° E	44 lks (29.04 feet)
Sugar	8"	N 79° W	29 lks (19.14 feet)

On 10/29/76 Arthur O. Enger RLS DNR found an old fence corner on the West side of a County Road marking the corner position. He set a 1" x 36" pipe with a 3 3/4" dia. aluminum cap, 8" above ground surface and stamped as follows:

DNR, T44N, R34W, S28, S29, S32, S33, RLS 13581. Recorded in Land Corner Certificate L. 1, Page 542 on 9/12/77.

1976 Bearing Trees:

Sugar Maple	9'	S 81° W	24.6 feet
Sugar Maple	6"	N 55° E	72.7 feet

PEER GROUP APPROVED

Gary L. Pisoni 12-19-97
IRON COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

On November 29, 1997, found monument as set by Authur O. Enger RLS in 1976 along with the following bearing trees:

Sugar Maple	11"	S 80° W	24.87 feet
Sugar Maple	8"dbl	N 54° E	72.83 feet

I accept the DNR monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (measurements taken to a nail in side of tree)

Sugar Maple	10"	S 63° W	11.13 feet
Sugar Maple	6"	S 20° W	23.64 feet
Steel sign post	6'	N 30° W	0.90 feet

97-10a
Signed by *Gary L. Pisoni*

Date December 16, 1997

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS: JAN 14 1971
REVISED MAY 14 1975
REVISED JAN 1983
REVISED OCT. 1995

