

**SURVEY & REMONUMENTATION**

**JAN 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

IRON COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 97 DEC 23 PH 1:30  
 L.C. Records L.P. 161  
*Richard Stiles*  
 REGISTER OF DEEDS

For corners in

Iron  
 (County)

Located in:

Corner Code #

- 1. Public Land Survey T 44N R 34W  
 T 43N R 34W  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

E-13 ✓  
 E-1  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Section Corner Sections 32, 33, T44N, R34W  
 Sections 4, 5, T43N, R34W

I, Gary L. Pisoni, in a field survey on November 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 Original corner established in 1846 by William A. Burt, U.S. Deputy Surveyor.  
 Original Corner: Maple Post  
 Original Bearing Trees:

Yellow Birch	18"	N 19° E	42 lks (27.72 feet)
Sugar	10"	N 08° W	22 lks (14.52 feet)

On 7/29/77, Arthur O. Enger RLS, DNR, found an old scribed white painted cedar post marking corner position. Position checks with other corners in the area. Set a 1" x 36" iron pipe with a 3 3/4" dia. aluminum cap stamped as follows: DNR, T44-43N, R34W, S32, S33, S5, S4, RLS 13581. Recorded in Land Corner Certificate L. 1, Page 542 on 9/12/77.

1977 Bearing Trees

Sugar Maple	5"	N 41° W	14.2 feet
Sugar Maple	4"	S 87° W	5.1 feet

PEER GROUP APPROVED  
*Gary L. Pisoni 12-19-97*  
 IRON COUNTY REPRESENTATIVE

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found..

On November 28, 1997, found monument as set by Arthur O. Enger RLS in 1977 along with the following bearing trees:

Sugar Maple	5"	N 53° W	14.32 feet
Sugar Maple	6"	S 76° W	5.13 feet

I accept the DNR monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Blazed and scribed the following new bearing trees: (measurement taken to a nail in side of tree)

Utility Pole	No. # on pole	N 87° E	30.43 feet
Balsam	8"	S 32° E	32.75 feet
Steel sign post	6'	S 32° W	0.90 feet

97-8a  
 Signed by *Gary L. Pisoni*

Date December 16, 1997

Surveyor's Michigan License No. 27457

