

**SURVEY &
REMONUMENTATION**

JAN 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD
97 DEC 23 PM 1:30
L.C. Records L. P. 162
Gilbert Stiles
REGISTER OF DEEDS

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 34W	<u>E-13</u> ✓
	T 43N R 34W	F-1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Section 33, T44N, R34W
Section 4, T43N, R34W

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Gary L. Pisoni, in a field survey on November 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by William A. Burt.
Original Corner: Sugar Post
Original Bearing Trees:
Sugar 14" N 50° E 17 lks. (11.22 feet)
Lynn 8" N 53° W 35 lks. (23.10 feet)

On 8/21/79, Arthur O. Enger RLS DNR reset the quarter corner by single proportionate measurement and on line between the Southwest and Southeast Section corners of Section 33. He set a 1" x 36" iron pipe with a 3 3/4" dia. aluminum cap, 6" above ground surface and stamped as follows: DNR, T44-43N, R34W, 1/4, S33, S4, RLS 13581. Recorded in Land Corner Certificate L. 2b, Page 5. on 3/10/80.

1979 Bearing trees:
Sugar Maple 9" N 19° W 21.5 feet
Sugar Maple 5" S 17° E 27.4 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.'s found.

PEER GROUP APPROVED
Gary L. Pisoni 12-19-97
IRON COUNTY REPRESENTATIVE

On 11/28/97, found monument as set by Arthur O. Enger in 1979 along with the following bearing trees:

Sugar Maple 9" N 18° W 21.91 feet
Sugar Maple 5" S 16° E 27.6 feet

I accept the DNR monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (measurements taken to a nail in side of tree)

Sugar Maple 12" N 28° E 16.92 feet
Sugar Maple 12" S 80° W 34.25 feet
Steel sign post 6' North 0.65 feet

97-9a
Signed by *Gary L. Pisoni*
Surveyor's Michigan License No. 27457

Date December 16, 1997



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 29, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1995