

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 97 DEC 23 PM 1:30
 L.L. Records L. 7 P. 165
Gilbert S. Pisoni
 REGISTER OF DEEDS

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>34W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner Common to Sections 27, 28, 33, 34, T44N, R34W

I, Gary L. Pisoni, in a field survey on November 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
 Original Corner: Wood Post
 Original Bearing Trees:

Yellow Birch	18"	S 40° W	53 lks (34.98 feet)
Yellow Birch	12"	N 45° E	16 lks (10.56 feet)

In 1949, Wickman & Peterson, Foresters for Northern Paper Mills, found original bearing trees and iron marks visible, set a post at corner position from the B.T.s

In 1953, Wickman & Peryam, Foresters for Northern Paper Mills, found post and set iron pipe with brass cap as recorded in Land Corner Certificate L. 2, Page 34.

On 5/26/77, Arthur O. Enger RLS DNR found the above described monument and restored said monument as recorded in Land Corner Certificate L.1, Page 493 on 8/5/77.

1977 bearing trees by Arthur O. Enger

Sugar Maple	5"	S 65 ½° W	23.7 feet
Sugar Maple	5"	S 53° E	2.4 feet

PEER GROUP APPROVED
Gary L. Pisoni 12-19-97
 IRON COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

On November 29, 1997, found monument as found by Arthur O. Enger on 5/26/77 along with the following bearing tree:

Sugar Maple	9"	S 45° E	2.56 feet
-------------	----	---------	-----------

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over the top of existing monument, set a 2" dia. by 30" long aluminum pipe monument, 3" above ground surface with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T44N, R34W, S28, S27, S33, S34, 1997, RLS 27457, blazed and scribed the following new bearing trees: (Measurements taken to a nail in side of tree)

Sugar Maple	8"	S 36° W	30.86 feet
Ironwood	4"	S 88° W	32.68 feet
Sugar Maple	8"	N 26° W	45.13 feet
Steel sign post		S 15° E	0.69 feet

97-12a
 Signed by Gary L. Pisoni
 Surveyor's Michigan License No. 27457

Date December 16, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, MAY 28, 1971
 27457 REVISED MAY 24, 1975
 REVISED JAN., 1983
 REUSED OCT., 1995

