

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>34W</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:13

L.C. Reggels: L, 8, P. 28
Richard Stibel
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner to Sections 26, 25, 35, 36, T44N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 5, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
Original Corner; Wood Post
Original Bearing Trees:

Sugar	14"	N 25° E	45 lks (29.70 feet)
Elm	12"	S 30° W	23 lks (15.18 feet)

PEER GROUP APPROVED
Iron County Rep. 12-21-99
COUNTY REPRESENTATIVE

On 6/6/77, Arthur O. Enger RLS, DNR, replaced a wood post and set a 1" diameter by 36" long iron pipe with a 3 3/4" aluminum cap stamped as follows: T44N, R34W, S-25, S-26, S-35, S-36, 6/6/77, RLS 13581, recorded in Liber 1, Page 540 of LC records.

1977 Bearing Trees:

Sugar Maple	6"	N 06° E	24.6 feet
Sugar Maple	8"	S 01° E	39.2 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/12/99, found the monument as described above and the following bearing trees:

Sugar Maple	7"	N 05° E	24.77 feet
Wood Post	3"	N 55° E	0.5 feet

Monument is 6" above ground surface.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	6"	N 46° E	39.05 feet
Sugar Maple	7"	S 34° E	23.27 feet
White Spruce	12"	N 76° W	12.68 feet
Sugar Maple	11"	N 14° W	38.67 feet
Steel sign post		West	0.75 feet

99-28
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

