

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>34W</u>	<u>K-13</u> ✓
	T <u>43N</u> R <u>34W</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:14

L.C. Records: L. 8, P. 29

Gary L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner to Sections 35 and 36, T44N, R34W
Section Corner to Sections 2 and 1, T43N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by Austin Burt, U.S. Deputy Surveyor.
Original Corner; Sugar Post
Original Bearing Trees:

Sugar	10"	N 59 1/2° E	46 lks (30.36 feet)
Lynn	18"	N 32° W	17 lks (11.22 feet)

On August 30, 1851, Guy H. Carleton, U.S. Deputy Surveyor established the following bearing trees:

Sugar	12"	S 75° E	48 lks (31.68 feet)
Sugar	9"	S 65° W	28 lks (18.48 feet)

On 8/16/79, Arthur O. Enger, RLS, DNR, restored the corner position by single proportionate measurement along the town line and set a 1" diameter by 36" long iron pipe with a 3 3/4" aluminum cap stamped as follows: T44N, R34W, S-35, S-36, S-2, S-1, T43N, 8/16/79, RLS 13581 recorded in Liber 2b, Page 9 of LC records.

1979 Bearing Trees:

Sugar Maple	15"	N 03° W	18.4 feet
Sugar Maple	12"	S 72° E	14.8 feet
Sugar Maple	13"	S 61° W	24.3 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/12/99, found the monument as described above and the following bearing trees:

Sugar Maple	13"	S 70° E	15.10 feet
Sugar Maple	15"	S 61° W	24.76 feet

Monument is 16" above ground surface.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	8"	N 41° W	14.58 feet
Sugar Maple	7"	N 40° E	49.33 feet
Steel sign post		West	1.2 feet

99-29

Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

PEER GROUP APPROVED
From Gary L. Pisoni 12-21-99
COUNTY REPRESENTATIVE

