

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

(County)

Located In:

Corner Code #

1. Public Land Survey

T	44N	R	34W	K5
T	44N	R	34W	MC north of I5
T		R		
T		R		

2. Property Controlling
in Section

S	T	R	
S	T	R	
S	T	R	
S	T	R	

3. Miscellaneous
Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jan 30 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K5) Corner common to Sections 11-12-13-14. 1976: Remonumented by A.O.Enger RLS at record bearing and distance from the remains of a W.Pine that he suspected was an original B.T. the position also agreed with record measurements to original corners North and South and to a river bank to the East. Set 1"IDx36" I.pipe with 3 3/4" aluminum cap. NBTs: W.Pine 18 N58E 98.6', W.Spruce 18 S14W 61.6'. (MC north of I5) Meander corner on the south bank of the Paint River between Sections 10 and 11. 1976: Remonumented in the original position by A.O.Enger RLS from the remains of an original BT. Set 1"IDx36" I. pipe with 3 3/4" aluminum cap. Silver Maple 12 S68E 35.3', Cedar 16 S55W 116.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K5) Recovered the 1976 monument, a 1"ID iron pipe with 3 3/4" dia. aluminum State of Michigan tablet, in good condition, and at record bearing and distance from the 1976 NBTs, both in good condition, and from the stump remains of the possible OBT noted by Enger in his 1976 record. Left the monument in place and made two new NBTs as described below. Two American Can Co. posters on nearby balsam firs face the monument.

(MC north of I5) Recovered the 1976 monument in good condition and at record bearing and distance from the 1976 NBTs, both found in good condition with overgrown blazes. Left the monument in place and made two new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K5) Found 1"ID I.pipe with aluminum State of Michigan cap. The 1976 NBTs: 22" dbl W.Pine N60E 98.6' scribe plain 20" W.Spruce S16W 61.6' overgrwn blazes Blazed, scribed and set meas. nails in: 12" W.Spruce S59E 51.25' "S13 NBT" 7" W.Spruce N62W 36.9' "S11 NBT" Bearings are magnetic. Distances to 2003 NBTs are to nail with plastic tag. 1976 dist. are to notch.

(MC) Found 1"ID I.pipe with 3 3/4" alum. State of Michigan cap. The 1976 NBTs: 12" Silver Maple S63E 35.3' 16" dbl Cedar S60W 116.8' Blazed, scribed and set measuring nails in: 12" Silver Maple S27E 33.2' "MC BT" 12" Silver Maple S15W 36.85' do Bearings are magnetic. Distances to 2003 NBTs are to meas. nail with tag. 1976 dist. are to notch.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 3/24/03