

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u>	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>44</u> N R <u>34</u> N	<u>I4</u>
	T <u>44</u> N R <u>34</u> N	<u>K4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Mar 17 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10	●	11	●	12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (I4) Quarter corner common to Sections 10-11. 1851: Established by Guy Carleton. S19'W corrected between Sections 10 and 11...40.105 Set quarter post. Y.Birch 20 N20W 37 links, Sugar 10 S40E 28 links...49.86 Over River to right bank and set meander post...80.21 Set post corner of Secs. 10,11,14, & 15.
 (K4) Quarter corner common to Sections 11-12. 1851: Established by Guy Carleton. S34'E corrected between Secs. 11 & 12...40.16 Set quarter post. sugar 10 S29E 39 links, sugar 10 N55W 12 links...80.32 Set post Cor. of Secs. 11,12,13 & 14. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (I4) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record between original corner positions for section corner 2648.46' north and for MC on south side of river 644.25' south.
 (K4) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record between perpetuated original section corner 2651.79' south and reestablished section corner 2651.79' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (I4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 8" Sugar N47E 18.0' "1/4S NBT"
 10" Y.Birch S22E 29.6' do
 8" Sugar S48W 30.25' do
 11" dbl Sugar N41W 39.6' do
 Set squared post adjacent. Bearings are magnetic. Distances are to nail with tag.
 (K4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 8" Maple N28E 21.5' "1/4S NBT"
 4" Sugar N80E 20.25' do
 6" dbl Maple S33E 28.6' do
 16" W.Spruce S67W 49.3' do
 Set squared post adjacent. Bearings are magnetic. Distances are to nail with plastic tag.



Signed by Stephan J. Szyszkoski Date 3/24/03
 Surveyor's Michigan License No. 33986