

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N	R 34W	I3
T 44N	R 34W	J3
T	R	
T	R	
T	R	

2. Property Controlling in Section

S	T	R	
S	T	R	

3. Miscellaneous Property in Sec.

S	T	R	
S	T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 31 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3									●	●			
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(I11) Corner common to Sections 2-3-10-11. 1976: Corner remonumented by A.O. Enger RLS from remains of original BT stump. Set 1"IDx36" iron pipe with 3 3/4" aluminum cap. Sugar Maple 4 S29W 51.7', W. Birch 14 S77E 11.6'.

(J3) Quarter corner common to Sections 2 and 11. 1977: Reestablished by A.O. Enger midway and on line between Section corners 39.725 chains east and west. Set 1"IDx36" I. pipe with 3 3/4" aluminum cap. Red Maple 7 S86W 27.1', Balsam 7 N44E 26.2'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I11) Recovered the 1976 monument in good condition and at record bearing and distance from the 1976 accessories. The Sugar is in good condition with overgrown blazes. The W. Birch is a dead standing stub with scribing visible. Left the monument in place and made three new witnesses as described below. The monument falls approximately 25' south of Parks Farm Road.

(J3) Recovered and accepted the 1976 monument in good condition, at record bearing and distance from the Maple NBT, and at the record position between section corners. The Maple NBT was found in good condition with overgrown blazes. The remains of the Balsam might yet exist but were not recovered, being obscured under the snow. Left the monument in place and made new witnesses as described below. The monument is about 40' south of Parks Farm Rd.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(I11) Found 1"ID I. pipe with alum. MDNR cap. Blazed, scribed, and set measuring nails in:

9" Y. Birch N10E 66.6'      "S2 NBT"  
 7" Maple in clump S47E 27.65'      "S11 NBT"  
 11" W. Spruce N23W 72.2'      "S3 NBT"

Bearings are magnetic. Distances are to nail with tag.

(J3) Found 1"ID I. pipe with alum. MDNR cap. Blazed, scribed, and set measuring nails in:

3" Spruce N63E 50.8'      "1/4S NBT"  
 4" Spruce S72E 50.0'      do  
 3" Sugar N45W 30.3'      do

Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/24/03