

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 34W	MC north of K8
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 24 T 44N R 34W	L8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23								
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on MC 05/14/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MC north of K8) Meander corner on the south bank of the Paint River, between Sections 23 and 24. 1977 - A.O. Enger RLS established and monumented a witness corner to this position on the South bank of the Paint river on the section line, about 1 ch. upstream from head of Lower Hemlock Rapids. Set 1"IDx36" I.pipe with 3 3/4" alum. MDNR cap. R.Maple 6" S38E 21.7', Cedar 11" S51W 28.8'.

(L8) Center of Section 24. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC) Recovered the 1977 monument in good condition and at record bearing and distance from the 1977 NBT Cedar SW, in good condition with scribing visible. The monument is located 1655.67' north of the Quarter corner of record between Sections 23 and 24 (1644.7' GLO record). This corner is being recorded to update the accessories.

(L8) Found a 1/2" dia. rebar with plastic cap stamped "Johnson 30083" at the intersection of 1/4 lines. Accepted same as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 12" Cedar S48W 28.9' (1977 NBT) 6" Balsam S82E 13.4' mrkd "MC NBT" 6" Sugar S17E 33.0' do 6" Cedar S03E 47.7' do Sq'd post adjacent. Bearings magnetic.	(L8) Fd 1/2" capped rebar PS 30083 Set measuring nail with MDNR tag in the side of: 12" Sugar N20E 41.2' mrkd "C1/4 BT 10" Sugar S55E 15.7' do 4" Spruce S07E 31.5' do 11" Sugar N70W 29.3' do Sq'd post adjacent. Bearings magnetic.
---	---

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/22/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

