

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 34W	I12
	T 44N R 34W	J11
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I12 04/22/2008

J11 04/23/2008

I, Stephan J. Szyszkoski, in a field survey on J11 04/23/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11										●			
12		31		32		33		34		●		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(I12) Quarter corner common to Sections 34-35. 1979 - Reestablished by A.O.Enger RLS on line between Section corners 39.7005 chains to North and South. Set 1"IDx36" I.pipe with 3 3/4" aluminum cap. Sugar Maple 12" N80E 37.0', Sugar Maple 10" S44E 28.0'.

(J11) Quarter corner common to Sections 26 and 35. 1977 - Reestablished by A.O.Enger RLS. Set 1"IDx36" iron pipe with 3 3/4" aluminum cap. Sugar Maple 6" N51W 28.5', Sugar Maple 6" S87W 10.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I12) Found the 1979 monument in good condition and at record bearing and distance from the 1979 witnesses trees. The NBT Sugar N80E is standing dead. The NBT Sugar SE is in good condition. This corner is being recorded to update the accessories.

(J11) Found the 1977 monument in good condition and at record bearing and distance from the 1977 witnesses, both in good condition with overgrown blazes. There is a typographical error in the record: The Sugar whose bearing is noted in the record as S87W is actually in the SE quadrant (S85E measured). This corner is being recorded to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I12) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 10" Sugar S41E 28.0' overgrown blazes (1979 NBT) 7" Sugar N43W 20.7' mrkd "1/4S NBT" 5" Sugar N09E 11.5' do 8" Sugar S73E 27.5' do Sq'd cedar post adjacent. Bearings magnetic.

(J11) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 8" Sugar N48W 28.6' old blazes (1977 NBT) 10" Sugar S85E 10.9' do do 6" Sugar N38E 19.6' mrkd "1/4S NBT" 11" Sugar S21W 6.8' do Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/22/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

