

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 35 T 44N R 34W	2
	S 24 T 44N R 34W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 05/13/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(2-Sec. 35) East 1/16 corner common to Sections 26 and 35. Not established in the original survey. 1977 - A.O.Enger RLS monumented the corner at a position derived from his speculation as to the location of the Section line based upon observation of the location of natural features noted in the original notes. Set 1" I.D. x36" iron pipe with 3 3/4" alum. cap. Sugar Maple 6" S66W 28.8', Cedar 9" N32W 36.6'.

(5-Sec. 24) North 1/16 corner, Section 24. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(2-Sec. 35) Recovered, but did not accept the 1977 monument as marking the proper position of the 1/16 corner. I reestablished the corner midway and on the Section line between Quarter corner 1310.95' west and Section corner 1310.95' east. From the position thus established, the 1977 monument bears approx. north, 36 feet distant. Removed the 1977 monument.

(5-Sec. 24) Established the corner midway and on a straight line between Center of Section 24 1318.98' to South and Quarter corner 1318.98' to North.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Sugar N15E 25.9' mrkd "1/16S BT"  
 12" Hemlock N39E 14.6' do  
 5" Sugar S40W 28.3' do  
 8" Sugar S70W 14.2' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Sugar N77E 4.15' mrkd "1/16S BT"  
 6" Maple S43E 7.8' do  
 5" Maple S09W 22.15' do  
 5" Balsam N83W 8.5' do  
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/22/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities