

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 34W	K8
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 24 T 44N R 34W	8
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	K8 05/15/2008	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23	●	24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 05/15/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K8) Quarter corner common to Sections 23-24. 1977 - A.O.Enger RLS reestablished the corner position on line between Section corners 39.972 chains to North and to South. Set 1"IDx36" I.pipe with 3 3/4" alum. cap. Red Maple 14" S25W 14.0', W.Birch 14" N22E 34.7'.

(8-Sec. 24) West 1/16 corner, Section 24. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K8) Recovered the 1977 monument in good condition and at record bearing and distance from the 1977 NBTs. The W.Birch is now a dead stub with rotted blazes. The Maple is in good condition with overgrown blazes. Verified the position of the monument with respect to the Section corners north and south and I accepted same as a careful and faithful reestablishment of the position of the original corner.

(8-Sec. 24) Found a 1/2" dia. rebar with plastic cap stamped "Johnson 30083" midway and on line between Center of Section 24 and West 1/4 corner of Section 24. Accepted same as a careful and faithful determination of the position of the corner. The corner falls in a Tag Alder swamp and is about 30' south of an E-W gravel road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>(K8) Fd. 1"I.D. I.Pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:                  14" Maple S30W 14.5' old blazes (1977 NBT)                  4" Spruce N42E 29.9' mrkd "1/4S NBT"                  4" Spruce S76E 15.0' do                  6" Aspen N41W 30.3' do                  Sq'd post adjacent. Bearings magnetic.</p>	<p>(8) Fd. 1/2" capped rebar PS 30083 Set measuring nail with MDNR tag in the side of:                  3" Balsam S22E 41.8' mrkd "1/16S BT"                  3" Spruce S36W 31.1' do                  3" Balsam N65W 42.1' do                  3" Balsam N16W 69.2' do                  Sq'd post adjacent. Bearings magnetic.</p>
---	---

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/22/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

