

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 34W	L7
	T 44N R 34W	L9
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on L7 05/15/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(L7) Quarter corner common to Sections 13-24. 1976 - A.O.Enger RLS reestablished the corner position substantially midway and on line between Section corners to East and West. Set 1"IDx36" I.pipe with 3 3/4" aluminum cap. W.Spruce 11" N24W 24.7', Red Maple 5" S52W 21.8'.

(L9) Quarter corner common to Sections 24-25. 1977 - Reestablished by A.O.Enger RLS midway and on line between Section corners 40.125 chains to east and west. Set 1"IDx36" I.pipe with 3 3/4" aluminum cap. Sugar Maple 10" S32W 84.5', Sugar Maple 12" N72E 71.7'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L7) Found the 1976 monument in good condition and at record bearing and distance from the 1976 witnesses. The W.Spruce is now dead and down, scribing visible. The Maple is in good condition with overgrown blazes. Verified the position of the monument with respect to monumented Section corners 1/2 mile to east and west and accepted same as a careful and faithful reestablishment of the position of the original corner.

(L9) Recovered the 1977 monument in good condition and at record bearing and distance from the 1977 witnesses. The Sugar NBT NE is now a stump. The Sugar NBT SW is in good condition with scribing visible. Found the monument to be S83E 1.3' from the midway position of record and accepted same as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L7) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 12" Maple S56W 22.0' old blazes (1976 NBT) 8" Maple S77E 53.0' mrkd "1/4S NBT" 8" double Maple S28W 31.1' do 5" Maple N58W 22.7' do Sq'd post adjacent. Bearings magnetic.

(L9) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 9" Sugar S36W 84.8' old marks (1977 NBT) 5" Maple N70E 38.2' mrkd "1/4S NBT" 4" Maple S64E 24.7' do 6" Maple in clump N45W 20.7' do Sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/22/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

