

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>35W</u>	<u>C-4</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:11  
L.C. Records: L. 8, P. 15

*[Signature]*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Section 7 and 8, T44N, R35W

I, Gary L. Pisoni, in a field survey on MARCH 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1851 by Harvey Mellen, U.S. Deputy Surveyor.  
Original Corner; Wood Post  
Original Bearing Trees:

Sugar Maple	10"	N 20°E	17 lks(11.22 feet)
Lynn	14"	S 76°W	12 lks(7.92 feet)

PEER GROUP APPROVED  
Iron Gary Pisoni 12-21-99  
COUNTY REPRESENTATIVE

On 09-20-68, Donald Lappala, cadastral surveyor, re-established corner position by single proportionate measurement on line between the recovered northwest and southwest corners of Section 8. Set a 2" inside diameter by 60" long concrete filled iron pipe, capped with a 3" circular bronze tablet which reads: T44N, R35W, 1/4, S-7, S-8; R.L.S .12585; 1968 and recorded in L.3, Pg.28.  
1968 Bearing trees:

Elm	11"	S 29°E	37.40 feet
Elm	13"	S 03°E	22.40 feet
Elm	12"	S 60°W	57.10 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 3-13-99, found monument as described above and the following bearing trees by unknown person:

Balsam	16"	S 52°E	32.35 feet
Sugar Maple	9"	S 11°E	18.93 feet
Sugar Maple	12"	S 73°W	65.55 feet
Steel sign post		N 29°W	2.50 feet

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing tree: (All measurements taken to a nail in side of tree)

Spruce	11"	N 19°W	34.97 feet
--------	-----	--------	------------

99-15  
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

