

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 35W	D-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:10
L.C. Records: L. 8, P. 14
Gary L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Section 5 and 8, T44N, R35W

I, Gary L. Pisoni, in a field survey on March 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3				●									
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1851 by Harvey Mellen, U.S. Deputy Surveyor.
Original Corner; Wood Post
Original Bearing Trees:
Cedar 10" N 04°E 49 lks(32.34 feet)
Spruce 12" N 22°E 56 lks(36.96 feet)

PEER GROUP APPROVED
Gary L. Pisoni 12-31-99
COUNTY REPRESENTATIVE

On 09-17-68, Donald Lappala, cadastral surveyor, restored corner position at record bearing and distance from several stream calls as shown in the original field notes. Set a 2" inside diameter by 60" long concrete filled iron pipe, capped with a 3" circular bronze tablet which reads: T44N, R35W, R.M., 1/4, S-5, S-8; 40.45' South; R.L.S.12585; 1968 and recorded in L.3, Pg.21.

1968 Bearing Objects:
4' X 5' X 2' boulder W/chiseled 'X' N 25°W 41.00 feet
2" diameter iron pipe(R.M.) North 40.45 feet
3' X 2' X 5' boulder W/chiseled 'X' N 46°E 37.40 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 3-13-99, found monument as described above and the following bearing trees by unknown person, bearing trees are to R.M.
Balsam 11" N 43°W 28.95 feet
Balsam 11" N 01°W 40.06 feet
Balsam 10" N 47°E 19.74 feet

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a new reference object:
Steel sign post East 1.25 feet

99-14
Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
No. 27457 REVISED JAN., 1983
REVISED OCT., 1995

