

SURVEY & REMONUMENTATION

JAN 12 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

95 DEC 15 PM 2:22
LC Records L.6, P. 419

Lillian Stebbins
REGISTER OF DEEDS

For corners in
Iron

(County)

Located In: Corner Code #

1. Public Land Survey

T 43N R 35W J-1
T 44N R 35W J-13

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Corner 2 & 35 T43-44N, R35W

I, Gary L. Pisoni, in a field survey on Sept. 12, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt, U.S. Deputy Surveyor in 1847.
Original corner: Wood post
Original bearing trees:
Cedar 8" N 30°E 35 links (23.10 feet)
Yellow Birch 16" N 62°W 36 links (23.76 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found. Found wood post and fence corner. GLO distance East and West check good. Accepted wood post as best available evidence for restoring corner position.

Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I replace wood post and set a 2"x30" split base aluminum pipe monument with 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43-44N, R35W, 1/4, S-2, S-35, 1995, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

White Birch	16"	N 25°E	33.41 feet
White Birch	9"	N 40°E	47.15 feet
Red Pine	20"	S 56°E	13.29 feet
Red Pine	18"	S 06°E	83.24 feet
Steel sign post		North	0.88 feet

PEER GROUP APPROVED
Iron County Surveyors 13-14-95
COUNTY REPRESENTATIVE

Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date 11-30-95

