

SURVEY & REMONUMENTATION

FEB 21 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>44N</u> R <u>34W</u>	<u>A-2,3s (006)</u>
	T <u>44N</u> R <u>35W</u>	<u>M-2,3s (002)</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

00 DEC -8 PM 1:04
L.C. Records, L. 8, P. 257
[Signature]
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

South Meander Corner to Section 1, T44N, R35W and Section 6, T44N, R34W

I, Gary L. Pisoni, in a field survey on April 5, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 15, 1846 by William A. Burt, U.S. Deputy Surveyor.
Original Corner; 16" diameter Cedar

On 10/1/75, Arthur O. Enger RLS DNR restored the corner position on true section line on the South bank of the Paint River. Set a 1" diameter by 36" long iron pipe with a 3 1/2" diameter aluminum cap, recorded in Liber 1, Page 514 of LC records.

1975 Bearing Trees:

Cedar	12"	S 27 W	77.1 feet
Cedar	6"	S 02 E	75.2 feet

In 1997, Patrick Leemon RLS USFS found the DNR monument located on the South edge of the Paint River and set a Witness corner to the Meander corner being an aluminum capped pipe monument stamped as follows: T44N, R35W, R34W, W.C.M.C., North, 18.12 feet, S-1, S-6, 1997, RLS 31595, recorded in Liber 1, Page 220-222 of survey maps.

1997 Bearing Trees:

White Spruce	8"	N 89 W	20.87 feet
White Spruce	21"	S 53 E	31.63 feet
White Birch	14"	S 11 E	8.87 feet
Cedar	14"	S 43 W	62.70 feet
Steel sign post		N 87 W	1.9 feet

PEER GROUP APPROVED

Gary L. Pisoni 11-30-2000
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of the original Meander Corner found.

On 4/5/2000, found the DNR monument located on the South edge of the Paint River, said monument is bent with aluminum cap missing. Also found the USFS monument as described above and the following bearing trees:

White Spruce	17"	S 54 E	31.63 feet
White Birch	14"	S 10 E	8.87 feet
Spruce	10"	N 87 W	20.88 feet
Steel sign post		N 87 W	2.0 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

00-025

Signed by Gary L. Pisoni Date 11-13-2000

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, NOV. 28, 1971

