

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>36W</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:08
L.C. Records: L. S. P. 4
Gary L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Section 7,8,17,18, T44N, R36W

I, Gary L. Pisoni, in a field survey on March 6, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on July 12, 1851 by Martin M. Hall, U.S. Deputy Surveyor.
Original Corner; Fir Post
Original Bearing Trees:

PEER GROUP APPROVED
Iron Aug Pisoni 8-24-99
COUNTY REPRESENTATIVE

Sugar Maple	14"	S 05°W	24 lks (15.84 feet)
Sugar Maple	12"	N 37°E	23 lks (15.18 feet)

On 10-18-84, Gary L. Pisoni, RLS, Re-established corner by double proportionate measurement methods and set a 2" diameter by 30" long split base aluminum monument with a 3" cast aluminum cap stamped to read: T.44N., R.36W., S-7,S-8,S-17,S-18; 1984; R.L.S. 27457, recorded in Liber 5, Page 124 of L.C. Records.

1984 Bearing Trees:

Sugar Maple	6"	N 75°30'E	17.05 feet
Sugar Maple	3"	S 51°W	7.06 feet
Black Cherry	10"	N 38°W	13.25 feet
Steel sign post		N 04°E	2.20 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.'s found. On 3-6-99 found monument as described above and the following bearing trees:

Sugar Maple	7"	N 75°30'E	17.08 feet
Sugar Maple	5"	S 53°W	7.06 feet
Steel sign post		N 05°E	2.20 feet

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	12"	N 14°W	22.53 feet
Sugar Maple	6"	S 55°E	13.05 feet

99-04
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
No. 27457 REVISOR, MAY 14, 1975
REVISED, JAN., 1983
REVISED, OCT., 1995

