

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>36W</u>	<u>C-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:09
L. C. Records, L. 8, P. 6
Gordon Stiles
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Section 17 and 18, T44N, R36W

I, Gary L. Pisoni, in a field survey on March 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18	•	17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on July 12, 1851 by Martin M. Hall, U.S. Deputy Surveyor.
Original Corner; Yellow Birch Post
Original Bearing Trees:

Hemlock	20"	N 31°W	29 lks (19.14 feet)
Sugar Maple	22"	S 35°E	51 lks (33.66 feet)

On 10-18-84, restored corner position by single proportionate measurement on line between the Northeast corner of Section 18 and the Southeast corner of Section 18 and set a 2 1/2" diameter by 30" long split base aluminum monument with a 3" cast aluminum cap stamped to read: T.44N.,R.36W., 1/4; S17, S-18; 1984; R.L.S. 27457, recorded in Liber 5, Page 125 of L.C. records.

1984 Bearing Trees:

Sugar Maple	6"	S 69°E	11.60 feet
Sugar Maple	7"	S 46°W	25.60 feet
Sugar Maple	4"	N 30°W	7.39 feet
Steel sign post		N 69°W	2.20 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 3-6-99 found monument as described above and the following bearing trees:

Sugar Maple	6"	S 62°E	11.62 feet
Sugar Maple	9"	S 49°W	25.60 feet
Sugar Maple	4"	N 24°W	7.38 feet
Steel sign post		N 62°W	2.20 feet

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing tree: (All measurements taken to a nail in side of tree)

Yellow Birch	11"	S 02°E	14.67 feet
--------------	-----	--------	------------

99-06
Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

PEER GROUP APPROVED
Iron Gary Pisoni 8-24-99
COUNTY REPRESENTATIVE

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983
REVISED OCT., 1995

