

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>36W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:09
L. C. Records, L. S., P. 7
Gary L. Pisoni
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Section 17,18,19,20, T44N, R36W

I, Gary L. Pisoni, in a field survey on March 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on July 12, 1851 by Martin M. Hall, U.S. Deputy Surveyor.
Original Corner; Hemlock Post
Original Bearing Trees:

Yellow Birch	18"	N 35°E	16 lks
Cedar	28"	S 70°W	29 lks

PEER GROUP APPROVE
Iron Gary Pisoni 8-24-99
COUNTY REPRESENTATIVE

On 07-18-67, Donald Lappala, cadastral surveyor restored corner position at record bearing and distance from remains of two original bearing trees and set a 2" diameter by 60" long concrete filled galvanized iron pipe, capped with a circular bronze tablet which reads: T.44N., R.36W., S-17, S-18, S-19, S-20; R.L.S. 12585; 1967, recorded in Liber 4, Page 31 of L.C. records.

1967 Bearing Trees:

Yellow Birch	N 10°W	45.10 feet
Elm	S 65°E	35.00 feet
Sugar Maple	N 55°W	25.70 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 3-6-99 found monument as described above and the following bearing trees:

Sugar Maple	8"	S 73°E	25.72 feet
Red Maple	13"	S 57°W	25.80 feet
Yellow Birch	8"	N 07°30'W	44.95 feet

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing tree: (All measurements taken to a nail in side of tree)

Balsam	7"	S 33°E	16.01 feet
Steel sign post		N 45°E	1.0 feet

99-07
Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
27457 REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

