

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>44N</u> R <u>36W</u>	<u>D-5</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:08  
*L.P. Reggolo, L.S., P. 5*  
*Gary L. Pisoni*  
SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Section 8 and 17, T44N, R36W

I, Gary L. Pisoni, in a field survey on March 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on July 12, 1851 by Martin M. Hall, U.S. Deputy Surveyor.  
Original Corner; Hemlock Post  
Original Bearing Trees:

Hemlock	24"	N 13°E	18 lks (11.88 feet)
Cedar	24"	S 65°W	42 lks (27.72 feet)

PEER GROUP APPROVED, 9  
*Iron Gary Pisoni 8-24-99*  
COUNTY REPRESENTATIVE

On 10-18-84, Gary L. Pisoni, RLS, restored corner position at record bearing and distance from the remains of two original bearing trees and set a 2 1/2" diameter by 30" long split base aluminum monument with a 3" cast aluminum cap stamped to read: T.44N., R.36W., 1/4; S-8, S-17; 1984; R.L.S. 27457, recorded in Liber 5, Page 113 of L.C. records.

1984 Bearing Trees:

Red Maple	6"	N 64°30'E	17.40 feet
Red Maple	8"	S 14°W	18.82 feet
Red Maple	7"	N 71°W	13.40 feet
Steel sign post		North	3.20 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 3-6-99 found monument as described above and the following bearing trees:

Red Maple	9"	N 64°30'E	17.41 feet
Red Maple	10"	S 14°W	18.84 feet
Red Maple	9"	N 71°W	13.43 feet
Steel sign post		North	3.30 feet

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing tree: (All measurements taken to a nail in side of tree)

Red Maple	7"	N 38°E	6.04 feet
-----------	----	--------	-----------

99-05  
Signed by *Gary L. Pisoni* Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

