

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>36W</u>	<u>K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:20

L.C. Records: L. 7, P. 289

Gilbert Stebbins
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sections 1 and 2, T44N, R36W

I, Gary L. Pisoni, in a field survey on Nov, 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2	●	1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1851 by Martin M. Hall, U.S. Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

Cedar	10"	N 75° E	7 links (4.62 feet)
Cedar	12"	S 48° W	4 links (2.64 feet)

On 7/3/67, Donald D. Lappala, RLS, U.S. Forest Service restored the corner position at record bearing and distance from the original bearing trees. He set a 2" diameter by 5' long galvanized iron pipe, 3 feet above ground surface, with a 3" brass cap stamped as follows: T44N, R36W, 1/4, S-1, S-2, 1967, RLS 12585 and recorded in L.C. certificate Liber 4, Page 18 on 4/9/68.

1967 Bearing Trees:

Spruce	5"	West	5.2 feet
Spruce	4"	North	23.0 feet
Spruce	3"	S 14° E	14.7 feet

PEER GROUP APPROVED
Alan Thomas 12-18-98
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found monument as described above and the following bearing trees:

Spruce	9"	West	5.00 feet
Spruce	6"	S 16° E	14.73 feet

I accept the above monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Spruce	7"	N 19° E	12.38 feet
Balsam	6"	N 26° W	10.08 feet
Steel sign post		S 45° W	0.80 feet

98-132
Signed by *Gary L. Pisoni* Date 12-21-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971
REVISED MAY 24, 1975
REVISED JAN. 1983
REVISED OCT., 1995



L. 7 P. 289