

# SURVEY & REMONUMENTATION

JAN 19 1999

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>36W</u>	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

98 DEC 28 AM 11:20  
*L.C. Records: L.7, P. 290*  
*[Signature]*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner Sections 1, 2, 11 and 12, T44N, R36W

I, Gary L. Pisoni, in a field survey on Nov. 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3											●		
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established in 1851 by Martin M. Hall, U.S. Deputy Surveyor.  
Original corner: Wood Post  
Original Bearing Trees:

Cedar	8"	N 31° W	16 links (10.56 feet)
Cedar	14"	S 49° E	22 links (14.52 feet)

On 7/3/67, Donald D. Lappala, RLS, U.S. Forest Service restored the corner position at record bearing and distance from the original bearing trees. He set a 2" diameter by 5' long galvanized iron pipe, 18 inches above ground surface, with a 3" brass cap stamped as follows: T44N, R36W, S-1, S-2, S-11, S-12, 1967, RLS 12585 and recorded in L.C. certificate Liber 4, Page 24 on 4/9/68.

1967 Bearing Trees:

Spruce	7"	N 4° E	30.7 feet
Cedar	10"	S 32° E	27.4 feet
Spruce	6"	S 87° W	31.5 feet

PEER REVIEW APPROVED  
Iron County Representative 12-18-98  
COUNTY REPRESENTATIVE

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of original B.T.s found. Found monument as described above and the following bearing trees:

Cedar	14"	S 30° E	27.20 feet
Spruce	9"	S 86° W	31.37 feet
Wood sign post		N 40° W	2.4 feet

I accept the above monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Black Spruce	9"	N 08° W	14.90 feet
Black Spruce	9"	S 76° E	14.81 feet
Steel sign post		N 50° E	0.95 feet

98-133

Signed by Gary L. Pisoni

Date 12-21-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
NO. 27457  
REVISED MAY 31, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995



L.7 P. 290