

**SURVEY &
REMONUMENTATION**

FEB 21 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

00 DEC -5 PM 12: 51

L.C. Regaulo, L.S., P. 229

Robert A. Goodreau
REGISTERED PROFESSIONAL SURVEYOR

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 36W T 44N R 36W T ___ R ___ T ___ R ___	J-1 J-13
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1										●			
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13										●			

I, Robert A. Goodreau in a field survey on May 11, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1/J-13 Original corner established by John Burt, U.S. Deputy Surveyor, in 1846.

Original witnesses: Tamarack 8" N 49° E 75 links
Tamarack 8" N 18.5° W 234 links

Donald D. Lappala RLS restored corner position on 13 April 1967 by setting a 6" long iron spike in centerline US 2, replacing local usage corner, which checked w/ original record distances to GLO corners ½ mile East and West. He also set a 2" X 5" concrete filled iron pipe reference monument w/ bronze tablet 27.22 feet South of corner (Liber 4, Page 51).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1/J-13 Found ½" iron pin in monument box, set by unknown surveyor.

Found reference monument set by Lappala at recorded distance (cap is missing).

Corner record research on file with county representative.

PEER GROUP APPROVED

Iron South of Person 11-30-2000
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1/J-13 Accepted corner as found.

Witnesses: Reference monument (5/8" iron pin w/ 3" aluminum cap) North 21.8'
Reference monument (5/8" iron pin w/ 3" aluminum cap) South 27.18'
9" Poplar S 60° E 62.24'
9" Poplar S 44° E 64.65'
Sign post 1' North of North Reference Monument

Note: Measurements taken to a nail in side of witnesses.



Signed by *R.A. Goodreau*
Surveyor's Michigan License No. 43053

Date July 1, 2000