

**SURVEY &
REMONUMENTATION**

FEB 21 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

00 DEC -5 PM 12: 51

L.C. Records: L. 8, P. 231

Richard A. [Signature]
REGISTER OF DEEDS

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 36W	L-1
	T 44N R 36W	L-13 ✓
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert A. Goodreau in a field survey on May 11, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-1/L-13 Original corner established by John Burt, U.S. Deputy Surveyor, in 1846.

Original witnesses: Spruce 3" N 64° E 24 links
Sugar Maple 5" N 69° W 34 links

Donald D. Lappala RLS restored corner position on 13 April 1967 from survey plat by I. N. Woodworth RLS. He verified retracement measurement to record natural feature calls to the East. Distance checked to Section corners to the East and West in accordance with original survey notes (Liber 4, Page 53).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1/L-13 Found 2" ID concrete filled iron pipe w/ 3" bronze tablet set by Lappala.

Found witness recorded by Lappala as: 8" x 9" Fence post S 50° E 5.1' (7.7 links)

Corner record research on file with county representative.

PEER GROUP APPROVED

Don Day of Pease 11/14/2000
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1/L-13 Accepted corner as found.

Witnesses: Fence post S 43° E 5.91'
4" Spruce N 25° E 19.76' (NBT)
3" Spruce S 67° E 4.78' (NBT)
3" Spruce S 30° W 8.08' (NBT)
Sign post South 1'

Note: Measurements taken to a nail in side of witnesses.

Signed by *R.A. Goodreau*
Surveyor's Michigan License No. 43053

Date July 1, 2000

