

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	<u>IRON COUNTY</u> LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>X</u> , R. <u>31</u> <u>K</u> W.	<u>G-4</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 10, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner between Sections 9 & 10, T45N, R31W

1" I.D. x 36" iron pipe with 4" aluminum cap, installed on 11-11-1970 by the undersigned, with following accessories:

*W. Spruce 16 N85°E (mag.) 22.0 ft. "1/4S, NBT"
Balsam 7 N14°E (mag.) 3.5 ft. "1/4S, NBT" (Destroyed)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Replaced the monument in A above, which had been destroyed by logging equipment, which also destroyed the Balsam 7 NBT. This corner had been restored on 11-11-1970 by the undersigned on line between Section Corners 39.94 ch. to N and to S. It lies on north-facing slope of a high ridge running ENE and WSW, about one chain north of the crest, as noted in original field notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
*W. Spruce 18 N88°E (mag.) 21.9 ft. "1/4S, NBT"
W. Pine 24 N37°W (mag.) 89.1 ft. "1/4S, NBT"
Distances are horizontal.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE March 15, 1974
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

