

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron-Marquette COUNTY
T 45 N R 30-31W

DESCRIPTION OF CORNER 1/4 corner between Sections 25 & 30

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 27, 1968

WITNESSES TO CORNER..... Cedar 14 N49W 79 lks. "1/4 S NBT"



White Birch 7 S14 1/2 W 25 1/2 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner placed in old N & S fence line in line with face scribed "BT" on a 5" W. Birch S60E 15 lks. from this position. Person who marked this tree is unknown, but ring count indicates the year of marking as about 1943. Found no evidence of a monument, but fence line appears to be on or very near to original section line as noted by calls to terrain features.

Corner is 4.43 chains north of N. shore of Fence Lake and the position checks quite well proportionately with the original field note calls to the lake shore and to the S. bank of a small stream north of the corner, and to an E & W county road reported to be on the north section lines of Sections 25 & 30.

No evidence of original corner or its accessories.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

2/12/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68