

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Marquette COUNTY


T 45 N R 30-31W

DESCRIPTION OF CORNER North 1/16 corner between Sections 31 & 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 7, 1968

WITNESSES TO CORNER..... Balsam Fir 6 S19°W 20 lks. "1/16 S BT"



Red Maple 7 West 30½ lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner established by proportionate measurement on line between Section Corner 19.98 chains North and 1/4 corner 19.98 chains South.

Found no evidence that a corner was ever established here previously.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR

DATE

2/14/69

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68