


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Iron-Marquette COUNTY
T 45N R 30-31W

DESCRIPTION OF CORNER N 1/16 corner between Sections 7 and 12
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED April 30, 1969
WITNESSES TO CORNER..... W. Spruce 5 N36°E 113½ lks. "1/16 S BT"



W. Spruce 10 S48°W 74½ lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between Section Corner 60.052 chains south and Township Corner 101.941 chains north. Found no evidence that a corner had ever been established here previously.

This corner falls in a depression east of a NE'ly trending ridge similar to one the top of which is recorded in the original field notes as being 60.00 chains north of the SE corner of Sec. 12. If the corner were placed about 60 links west of the position selected here, it would fall very near the top of this ridge. This raises a doubt as to whether the monument found at the SE corner of Sec. 12 is in fact the original corner. As proof to the contrary is difficult, the SE corner of Sec. 12 was left to stand as found.

Variation at this corner is about 2°15' West.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 10/20/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68