

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES  
LAND CORNER RECORD

Iron-Marquette COUNTY


T 45N R 30-31W

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 6

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 30, 1969

WITNESSES TO CORNER..... B. Spruce 6 S21°E 41 lks. "1/4S NBT"



Tamarack 14 N76°E 74 lks. "1/4S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between Section Corner 120.105 chains south and Township Corner 41.888 chains north. Found no evidence of original corner or its accessories or of any replacement monument or accessories. Position lies 4.08 chains south of a swamp edge reported in original field notes as being 4.50 chains north of the corner.

Variation at this corner is about 3°00' West.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR

DATE

10/20/69

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68